



## Y-12 Criticality Alarm System Testing with Godiva

Chris Haught  
Chief NCS Engineer

# Outline

## Purpose of testing – qualifying CAAS detectors

- Configuration of Y-12 Legacy CAAS
- Historic Qualification
  - Previous Reactor Testing Results
- Reactor Testing with Godiva
- Conclusions

# Legacy CAAS Configuration

- Gamma sensitive NMC GA-6 detectors
  - Plastic scintillators
  - PMTs
  - 30 +2/-5 mR/hr setpoint
  - Light source creates ~1 mR/hr artificial background
- Detector states
  - Normal
  - “Fail” (< ~0.1 mR/hr)
  - “Hi Rad” (above setpoint)
- CAAS Station
  - 2 detectors
  - Control relay circuit
  - Alarms on 2 “Hi Rad” signals
- Accident Coverage
  - Generic 400-ft range of coverage
  - “Overlapping” coverage required




# Overlapping CAAS Coverage

400-foot range of coverage for each station

All fissile material areas within the range of at least 2 stations

Each CAAS station  has 2 detectors




# Overlapping CAAS Coverage

400-foot range of coverage for each station

Each CAAS station  has 2 detectors

Postulated  criticality accident




# Overlapping CAAS Coverage

400-foot range of coverage for each station

Each CAAS station  has 2 detectors

Postulated  criticality accident




# Overlapping CAAS Coverage

400-foot range of coverage for each station

Each CAAS station  has 2 detectors

Postulated  criticality accident

Accident seen by 2 stations



# Historic CAAS Detector Qualification and Maintenance

- History of pulse reactor testing dating back to 1950s
  - Range of accident coverage
  - Detector qualification
- Detector checks
  - “Fail” indicator monitoring
  - Periodic visual checks
  - Periodic source checks
- Detectors require periodic calibration due to setpoint drift
  - Y-12 maintains an onsite calibration facility
  - Detectors periodically removed from service and replaced with ones recently calibrated
  - Removed detectors are recalibrated and queued reuse

# Previous Reactor Testing


- Basis for generic range of coverage
  - Testing at ORNL, SNL, and LANL
  - Rudimentary shielding calculations
  - Expert judgment

## SHEBA 1994 (most recent)


Dose <sup>1</sup> @ 2 m (rad)	Peak Dose <sup>1</sup> Rate @ 2 m (rad/min)	Distance (ft)	Shielding	Alarms <sup>2</sup>
38	38	800	None	3/3
4.3	12	400	2 clay tiles	3/3
7.2	43	400	3 clay tiles	3/3
11	37	400	2 concrete blocks	1/1

1: Combined gamma and neutron doses

2: Units that alarmed / units available to alarm



94 NOV 10 A 400 ft



94 NOV 8 B 400 ft  
3 clay tile wall -  
"All Alarmed"

# Previous Reactor Testing

- Detector Qualification (ANSI/ANS-8.3)
  - Minimum accident of concern (20 rad/m @ 2 m or alternate)
  - Response to minimum duration transient (1 ms)
  - Tolerance to maximum radiation (10 rad/s)
- Detector qualification criteria from 1980s
  - $10^{15}$  fissions 800 feet from detector (distant pulse test)
  - $10^{17}$  fissions 14 feet from detector (intense pulse test)
  - Required for every detector

# Previous Reactor Testing

## Qualification Testing from 1980s-1990s

### Godiva IV Test Results (April 1989)

Distance (ft)	Pulse Width (FWHM) ( $\mu$ s)	Fissions	Dose <sup>1</sup> @ distance (rad)	Dose <sup>1</sup> Rate @ distance (rad/s)
32 of 32 detectors alarmed				
12	40	$3.23 \times 10^{16}$	133	$3.31 \times 10^6$
1600	3,500	$3.54 \times 10^{14}$	$8.18 \times 10^{-5}$	0.0234
1600	2,000	$1.57 \times 10^{15}$	$3.64 \times 10^{-4}$	0.182

1: Combined gamma and neutron doses

### SPR-III Test Results (March 1992)

Pulse Width (FWHM) (ms)	$\Delta T$ ( $^{\circ}$ C)	Fissions <sup>1</sup>	Dose <sup>2</sup> @ 3 m (rad)	Dose <sup>2</sup> Rate @ 3 m (rad/s)
Detectors located 12' 8" from reactor; 63 of 63 detectors alarmed				
2.59	41	$2.73 \times 10^{16}$	101	$3.88 \times 10^4$
2.79	42	$2.80 \times 10^{16}$	103	$3.70 \times 10^4$
1.54	50	$3.33 \times 10^{16}$	123	$7.94 \times 10^4$
Detectors located 722' from reactor; 54 of 63 detectors alarmed				
0.382	95	$6.33 \times 10^{16}$	349	$9.14 \times 10^5$
0.442	98	$6.53 \times 10^{16}$	338	$7.65 \times 10^5$
0.348	99	$6.60 \times 10^{16}$	356	$1.02 \times 10^6$

1: Based on 150 $^{\circ}$ C corresponding to  $1 \times 10^{17}$  fissions  
 2: Combined gamma and neutron doses

## Y-12 CAAS Post 1990s

- DOE no longer has an operational fast pulse reactor (until circa ~2010)
- New detectors purchased in 2005
- New PMTs purchased in 2016
- Detector qualification only involves passing calibration process
  - Setpoint equivalent to radiation level at 400 feet from a 20 rad/min @ 2m source (shielding from 3 hollow clay tile walls or 12 inches of concrete)
  - Lacking qualification for maximum radiation and minimum pulse width
- Recent assessment discovered some detectors in service that were tested in 1992 and had inconclusive results reported

# Godiva IV Testing

- Subject “sample” of detectors to an intense pulse at close range
  - Maximum expected radiation
  - Minimum pulse width
- 6 detectors tested
  - 2 new detectors
  - 4 existing detectors with replacement PMTs
- Data Logging
  - Data logger in control room
  - Output voltage from each detector connected to data logger
  - Contact closure signal from each detector connected to data logger
  - Signal from reactor acquired to record time of burst

# Godiva IV Testing

- Configuration
  - Detectors positioned within an arc around the reactor
  - DC power supplied to each detector
  - 180 cm above the floor
  - 2 meters from the reactor core centerline
  - NADs and  $\text{CaF}_2(\text{Mn})$  dosimeters placed in similar locations
- Schedule
  - Equipment set-up on day 1
  - 95¢ pulse on day 2 to confirm detector operability and data connections
  - Prompt pulses of increasing magnitude on days 2, 3, and 4
- Data measurements
  - Temperature rise from RTDs
  - Reactivity and fission yield determined from relationship with  $\Delta T$
  - Pulse width (FWHM) from PD output trace
  - Dose from relationship with  $\Delta T$  (IER-147)
  - Dose rate from total dose integrated over pulse shape (PD output trace)

# Godiva IV Testing

## Results

Burst #	Reactivity ( $\rho$ above prompt)	Burst Temp. ( $\Delta T$ °C)	Fission Yield ( $\times 10^{16}$ fissions)	Pulse Width FWHM <sup>§</sup> ( $\mu$ sec)	Total Absorbed Air Dose* and Dose Rate at 2 m from Godiva IV		CAAS Alarm Response <sup>¥</sup>
					Dose (Rad)	Dose Rate <sup>§</sup> (MRad/s)	
2025	0.8	47.5	0.63	970	28 (14 n + 14 $\gamma$ )	.017	Immediate
2026	3.0	71.8	0.95	310	42 (20 n + 22 $\gamma$ )	0.10	Immediate
2027	8.0	149.0	2.0	180	86 (42 n + 44 $\gamma$ )	0.35	Immediate

# Conclusion

- Re-established DOE capability to test detectors with intense, short-duration mixed neutron and gamma field
- Established confidence that new detectors and existing detectors with new PMTs:
  - Will detect a minimum duration criticality accident
  - Are tolerant to maximum radiation
- Fielded dosimetry agreed with IER-147 within 25%
- Future work
  - Re-test detectors from 1992
  - Re-test detectors purchased in 2005
  - Simulate distant pulse?

# Acknowledgments

- DOE NCSP for overall support and funding
- LLNL for planning, dosimetry, and results
- LANL for setting up equipment and operating reactor

## Disclaimer

This work of authorship and those incorporated herein were prepared by Consolidated Nuclear Security, LLC (CNS) as accounts of work sponsored by an agency of the United States Government under Contract DE-NA0001942. Neither the United States Government nor any agency thereof, nor CNS, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility to any non-governmental recipient hereof for the accuracy, completeness, use made, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency or contractor thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency or contractor (other than the authors) thereof.